HOJA DE DATOS PARA BOMBA DE TORNILLO DOBLE (EF)

REV.	FECHA	PÁG	DESCRIPCIÓN	ELAB	REV. / APROB.	APROB. ICHQ	APROB. PSSA
0	28/12/2012	4	EMISIÓN FINAL	GXD	ZYB/XGK		
A	24/05/2012	4	EMISIÓN PARA COMENTARIOS	GXD	ZYB/XGK		

DERECHOS RESERVADOS

Este documento es propiedad de PSSA. No se permite la divulgación u otro uso de este documento sin la previa autorización escrita de PSSA.

No. Documento HQCEC	5083E-04-2000-M10-420-001
Archivo Electrónico:	FF-D-178-12-2212-S201-0

PDVSA PETROLERA SINOVENSA	DESARROLLO DE LA INGENIERÍA CONCEPTUAL Y BÁSICA DEL PROYECTO DE EXPANSIÓN DE PRODUCCIÓN DE 105 MBD A 160 MBD	PDVSA INGENIERÍA Y CONSTRUCCIÓN HQCEC

N° Documento PSSA :	N° Proyecto :	Página :	N° Proyecto ICHQ:	Fase del Proyecto	N° Documento ICHQ :	Rev.
FF-D-178-12-2212-S201	178	2 de 4	5083E	Básica	5083E-1-FFX-D-1131-M1D-HDE-0001	0

SCREW PUMP DATA SHEET

APPLICABLE TO: O PROPOSAL ● PURCHASE O AS BUILT

CLIENT: PSSA

SITE: MORICHAL

SERVICE: WDEHO TRANSFER PUMPS

MANUFACTURER:

ITEM TAG: 0002-P-1002A/B/C/D/E

PLANT: FS

NO. OF PUMPS REQUIRED: FOUR (4) OPERATING AND ONE (1) SPARE

SIZE AND TYPE: HORIZONTAL TWIN-SCREW PUMP

SERIAL NO.

LEYEND: O INDICATES INFORMATION TO BE COMPLETED BY PURCHASER □ BY MANUFACTURER

GENERAL

NO. MOTORS DRIVEN:
PUMP ITEM NO'S: 0002-P-1002A/B/C/D/E
MOTOR ITEM NO'S:
MOTOR PROVIDED BY:
MOTOR MOUNTED BY:
MOTOR DATA SHEET NO.:

OTHER DRIVER TYPE
PUMP ITEM NO'S
DRIVER ITEM NO'S
DRIVER PROVIDED BY
DRIVER MOUNTED BY
DRIVER DATA SHEET NO.

GEAR ITEM NO'S
GEAR PROVIDED BY
GEAR MOUNTED BY
GEAR DATA SHEET NO.

OPERATING CONDITIONS

- CAPACITY @ PT (GPM US): RANGE NORMAL 2145 RATED 2359.5
- DISCHARGE PRESSURE (psig): MAXIMUM: 383.7 MINIMUM: 281.0
- SUCTION PRESSURE (psig): MAXIMUM: 14.4 MINIMUM: 3.5
- DIFFERENTIAL PRESSURE (psi): MAXIMUM: 380.2 MINIMUM: 266.6
- NPSH AVAILABLE (ft.) 8.54 (NOTE2)
- SERVICE ● CONTINUOUS O INTERMITTENT

LIQUID

- TYPE OR NAME OF LIQUID: WET DILUENT EXTRA HEAVY OIL (NOTE3)
- PUMPING TEMPERATURE (°F): NORMAL: 100 MAX: 120 MIN: 90
- SPECIFIC GRAVITY: NORMAL 0.953 MAXIMUM 1 MINIMUM 0.94
- SPECIFIC HEAT Btu/lb °F
- VISCOSITY (cP): 442@ 100 °F MINIMUM 640.4@ 90 °F MAXIMUM
- VAPOR PRESSURE@ P.T. (psia) 14.7@ 100 °F
- O CORROSIVE/EROSIVE AGENTS:
- CHLORIDE CONCENTRATION (PTB) NaCl: 689 ~ 848 PTB
- O H_2S CONCENTRATION (PPM)

LIQUID: O TOXIC ● FLAMMABLE O OTHER

PERFORMANCE

- □ RATED CAPACITY (GPM US)
- □ NPSH REQUIRED (ft.)
- □ RATED SPEED (RPM)
- □ DISPLACEMENT (GPM)
- □ VOLUMETRIC EFFICIENCY (%)
- □ MECHANICAL EFFICIENCY (%)
- □ BHP @ MAXIMUM VISCOSITY
- □ BHP @ RELIEF VALVE SETTING
- □ MAXIMUM ALLOWABLE SPEED (RPM)
- □ MINIMUM ALLOWABLE SPEED (RPM)

SITE AND UTILITY DATA (NOTE 1)

LOCATION: O INDOOR ● OUTDOOR O SUN
O HEATED ● UNHEATED O UNDER ROOF
● ELECTRICAL AREA CLASS 1 GROUP D DIV: 2
O WINTERIZATION REQD ● TROPICALIZATION REQD

SITE DATA :
O RANGE OF AMBIENT TEMPS:MIN/MAX : / °F

UNUSUAL CONDITIONS
O DUST O FUMES ● SALTY ATMOSPHERE
O OTHER
O UTILITY CONDITIONS

	DRIVERS	HEATING	CONTROL	SHUTDOWN
ELECTRICITY				
VOLTAGE				
HERTZ				
PHASE				

COOLING WATER	INLET	RETURN	DESIGN	MAX Δ
TEMP °F		MAX		
PRESS. (psig)		MIN		
SOURCE				

INSTRUMENT AIR	MAX	MIN
PRESSURE (psig)		

CONSTRUCTION

CONNECTIONS	SIZE	RATING	FACING	POSITION
SUCTION				
DISCHARGE				
GLAND FLUSH				
DRAINS				
VENTS				
JACKET				

PUMP TYPE:
□ INTRN'L GEAR ■ TWIN-SCREW □ VANE
□ EXTRN'L GEAR □ 3-SCREW □ PROGRESSING CAVITY

GEAR TYPE
□ SPUR ■ HELICAL
□ OTHER

APPLICABLE SPECIFICATIONS:

- API 676 POSITIVE DISPLACEMENT PUMPS - ROTARY (latest edition)
- PDVSA GA-202
- OTHERS SPECIFIED IN THE MATERIAL REQUISITION

PDVSA PETROLERA SINOVENSA	DESARROLLO DE LA INGENIERÍA CONCEPTUAL Y BÁSICA DEL PROYECTO DE EXPANSIÓN DE PRODUCCIÓN DE 105 MBD A 160 MBD	PDVSA INGENIERÍA Y CONSTRUCCIÓN HQCEC

N° Documento PSSA :	N° Proyecto :	Página :	N° Proyecto ICHQ:	Fase del Proyecto	N° Documento ICHQ :	Rev.
FF-D-178-12-2212-S201	178	3 de 4	5083E	Básica	5083E-1-FFX-D-1131-M1D-HDE-0001	0

PROGRESSIVE CAVITY PUMP DATA SHEET

CONSTRUCTION (CONTINUED)

CASING (NOTE7)

- ☐ MAXIMUM ALLOWABLE PRESSURE: _____ kPa @ ____ °F
- ☐ HYDROSTATIC TEST PRESSURE: _____ kPa @
- ☐ STEAM JACKET PRESSURE: _____ kPa @ ____ °C

ROTOR MOUNT: ☐ BTWN. BEARINGS ☐ OVERHUNG

TIMING GEARS ☐ YES ☐ NO

BEARING TYPE: ☐ RADIAL _____ ☐ THRUST ____

LUBRICATION TYPE: ■ CONSTANT LEVEL OILERS

- ☐ PUMPED FLUID ☐ RING OIL ☐ OIL MIST
- ■ EXTERNAL ■ OIL FLOOD ☐ GREASE

- ☐ LUBRICANT TYPE: _____
- ● MECHANICAL SEALS: YES
  - ☐ MANUFACTURER AND MODEL _____
  - ☐ MANUFACTURER CODE _____
- ■ API 610 SEAL FLUSH PLAN 32+61 (NOTE5)
- ☐ API 610 SEAL CODE _____
- ○ PACKING: ☐ LANTERN RING
  - ○ MFR. AND TYPE _____ ○ NO. OF RINGS _____

DRIVE MECHANISM

■ DIRECT-COUPLED ☐ V-BELT ☐ GEAR

☐ COUPLING MANUFACTURER _____

DRIVERS

MOTOR :

- ☐ MANUFACTURER _____
- ☐ TYPE _____
- ☐ FRAME NO. _____
- ☐ NEMA DESIGN _____
- ☐ APPROVAL, LISTED OR CERTIFIED BY: _____
- ○ CONSTANT SPEED _____
- ○ VARIABLE SPEED _____
- ☐ HP _____ RPM _____
- ● VOLTS 4160 PHASE 3
- ● HERTZ 60 SERVICE FACTOR _____
- ● ENCLOSURE TEFC
- ○ MINIMUM STARTING VOLTAGE _____
- ● STARTING METHOD Automatic
- ○ INSULATION _____ ○ TEMPERATURE CLASS _____
- ☐ CONSECUTIVE STARTS _____
- ☐ MOTOR WINDING MATERIAL _____

MAIN JUNCTION BOX:

- ○ CONDUIT INPUT _____ ☐ QUANTITY _____
- ☐ SIZE _____

SPACE HEATERS JUNCTION BOX:

- ○ CONDUIT INPUT _____ ☐ QUANTITY _____
- ☐ SIZE _____
- ○ STEAM TURBINE

REMARKS _____

OTHER PURCHASER REQUIREMENTS

NAMEPLATE UNITS ● ENGLISH ○ SI

● RELIEF VALVES BY PUMP MFRG ○ INTERNAL ● EXTRNL (NOTE4)

PIPING FOR SEAL FLUSH FURNISHED BY:

● PUMP VENDOR ○ OTHERS

PIPING FOR COOLING/HEATING FURNISHED BY:

○ PUMP VENDOR ○ OTHERS

○ PROVIDE TECHNICAL DATA MANUAL

MATERIALS (NOTE6)

- ☐ CASING CS
- ☐ STATOR _____
- ☐ COMMON BASE PLATES _____
- ☐ ROTOR (S) CS
- ☐ VANES _____
- ☐ SHAFT _____
- ☐ SLEEVE (S) _____
- ☐ GLAND (S) _____
- ☐ BEARING HOUSING _____
- ☐ TIMING GEARS _____
- ○ SPECIAL MATERIAL TESTS (2.9.1.3) _____
- ○ LOW AMBIENT TEMP. MATERIALS TESTS (2.9.5)

QA INSPECTION AND TEST

- ● COMPLIANCE WITH INSPECTORS & TEST PLAN
- ○ CERTIFICATION OF MATERIALS
- ○ FINAL ASSEMBLY CLEARANCES
- ○ SURFACE AND SUBSURFACE EXAMINATIONS
  - ○ RADIOGRAPHY _____
  - ○ ULTRASONIC _____
  - ○ MAGNETIC PARTICLE _____
  - ○ LIQUID PENETRANT _____
- ○ CLEANLINESS PRIOR TO FINAL ASSEMBLY
- ○ HARDNESS OF PARTS, WELDS & HEAT AFFECTED ZONES
- ○ FURNISH PROCEDURES FOR OPTIONAL TESTS

TESTS	REQ'D	WIT	OBS
HYDROSTATIC	○	○	○
MECHANICAL RUN	○	○	○
PERFORMANCE	○	○	○
NPSH	○	○	○

PREPARATION FOR SHIPMENT

○ DOMESTIC ● EXPORT

● OUTDOOR STORAGE MORE THAN 6 MONTHS

WEIGHTS (kg)

☐ PUMP _____ ☐ BASE _____ ☐ DRIVER _____

☐ COUPLING ☐ ACCESSORIES

BASEPLATE

● BY PUMP MANUFACTURER ○ SUITABLE FOR EPOXY GROUT

○ EXTENDED FOR _____

● COMMON PLATES BY PUMP MANUFACTURER

○ DRAIN ☐ DRAIN-RIM

■ DRAIN-PAN

PDVSA PETROLERA SINOVENSA	DESARROLLO DE LA INGENIERÍA CONCEPTUAL Y BÁSICA DEL PROYECTO DE EXPANSIÓN DE PRODUCCIÓN DE 105 MBD A 160 MBD				PDVSA INGENIERÍA Y CONSTRUCCIÓN HQCEC	
N° Documento PSSA : FF-D-178-12-2212-S201	N° Proyecto : 178	Página : 4 de 4	N° Proyecto ICHQ: 5083E	Fase del Proyecto Básica	N° Documento ICHQ : 5083E-1-FFX-D-1131-M1D-HDE-0001	Rev. 0

PROGRESSIVE CAVITY PUMP DATA SHEET

NOTES

1 See Document "PROCESS DESIGN BASIS FOR MORICHAL" for detail. Because no cooling water is applicable, vendor shall consider air cooling for pump bear housing and flushing plan etc., where cooling is necessary. Tropicalization is required.

2 For the value of NPSHa, the pumps shall be able to operate with 0.5%(mol) disolved gas.

3 WDEHO is a mixture of extra heavy oil, diluent(naphtha) and water 12%(V), it is flammable. The fluid containing sands.

4 External safety valves shall be supplied by vendor, the design pressure of downstream pipe is 429 Psig.

5 The mechanical seal flushing plan shall be confirmed by vendor.

6 The material shall be confirmed by vendor.

7 Pump casing drain shall be connected to the edge of baseplate with block valve.

8 The estimated hydraulic power is 516.4 HP.