BHAGYANAGAR GAS LIMITED

(A JOINT VENTURE OF HPCL & GAIL)

BID DOCUMENT FOR

Comprehensive Annual Maintenance Contract (AMC) Services for M/s ICL/SAFE make Booster Compressors and CNG Dispensers at Hyderabad, Vijayawada and Kakinada

UNDER OPEN DOMESTIC COMPETITIVE BIDDING IN TWO BID SYSTEM

Bid Document No.: BGL/399/2017-18

VOLUME-II of II

CONTENTS

VOLUME II OF II

Section 7 : Service Requisition.

Section 8 : Scope of Work.

Section 9 : Special Conditions of Contract.

Section 10 : Schedule of Rates / Price Schedule.

SECTION 7

SERVICE REQUISITION

Service requisition for Comprehensive AMC of Booster Compressors (SAFE / ICL make):

S.No	Station name	Make of Compressor	Proposed Period (Months)
1	M/s. Hayath Filling Staion, Hayath nagar,Hyderabad (26.02.2018 to 25.02.2020)	(M/S. SAFE OR ICL make)	24
2	Sapthagiri Filling Station, Meerpet, Hyderabad(26.02.2018 to 25.02.2020)	(M/S. SAFE OR ICL make)	24
3	Lalitha Devi Petrol Pump, RP Road, Hyderabad(26.02.2018 to 25.02.2020)	(M/S. SAFE OR ICL make)	24
4	Sri Chakra Filling Station, Nampally, Hyderabad(26.02.2018 to 25.02.2020)	(M/S. SAFE OR ICL make)	24
5	Sri Srinivasa Service Station, Ramavarappadu, (02 nos.) Vijayawada(26.02.2018 to 25.02.2020)	(M/S. SAFE OR ICL make)	24
6	Ravindra Oil Company, Bhavanipuram, Vijayawada(26.02.2018 to 25.02.2020)	(M/S. SAFE OR ICL make)	24
7	Radhakrishna Service Station, Tadepalli, Vijayawada(26.02.2018 to 25.02.2020)	(M/S. SAFE OR ICL make)	24
8	South Central Railways, Diesel loco shed (as per the EIC intimation)	(M/S. SAFE OR ICL make)	24
9	APSRTC, Ibrahimpatnam-II Depot (02 nos. Boosters), Vijayawada (26.02.2018 to 25.02.2020)	(M/S. SAFE OR ICL make)	24
10	JP Fuels, Cinema Road, Kakinada(01.09.2015 to 31.08.2017)	(M/S. SAFE OR ICL make)	24
11	M/s. Swami auto care Nadakuduru, Kakinada (26.02.2018 to 25.02.2020)	(M/S. SAFE OR ICL make)	24

Service requisition for Comprehensive AMC of Car / Bus Dispensers (SAFE / ICL make):

S.No	Station name	Make of Dispenser	Proposed Period (Months)
1	BGL Mother Station (02 nos. Dispensers), Vijayawada(26.02.2018 to 25.02.2020)	M/S. SAFE OR ICL make)	24
2	Sri Srinivasa Service Station, Ramavarappadu, Vijayawada(26.02.2018 to 25.02.2020)	M/S. SAFE OR ICL make)	24
3	Basaveswara Filling Station, Ajitsingh Nagar (02 nos. Dispensers), Vijayawada(26.02.2018 to 25.02.2020)	M/S. SAFE OR ICL make)	24

SECTION 8

SCOPE OF WORK

General Scope of Work:

The Contractor must follow the Operation & Maintenance requirement as stated below but not limited to and ensure to provide trouble free services to the satisfaction of the owner.

1. Accommodation / transportation / medical

The contractor shall make his own arrangement for the accommodation of his personnel at respective locations and subsequent transportation arrangement for them from their place of residence to work place or any other place as required and company shall have no obligation in this respect. The company shall not be responsible for providing any medical assistance to the contractor personnel.

2. Discipline

The Contractor shall be responsible for the discipline and good behaviour of all his personnel deployed in the services contracted out and should any compliant be received against any of his employee; he shall arrange to replace such persons within 24 hours of notice issued by the Engineer-in-Charge. The decision of the Engineer-in-Charge in this matter shall be final and binding on the contractor.

3. Gate pass / identity card

The contract shall arrange to supply / renew identity card to his workforce at his own cost, if so required by BGL for security or for any other reasons. Those contractor's personnel shall be required to carry their respective identity cards while on duty and produce on demand.

4. Right to get services carried out through their agencies

Nothing contained herein shall restrict BGL from accepting similar services from other agencies, at its discretion and at the risk and cost of the contractor, if the contractor fails to provide the said services any time.

5. Sub-letting of contract

No part of this contract nor any share or interest therein in any manner or extent, will be transferred or assigned or sub-let, directly or indirectly to any person / firm or Organization without prior permission of BGL.

6 The officer in charge shall have power to

i) Issue the Contractor from time to time during the running of the contract such further instructions as shall be necessary for the purpose of proper and adequate execution of the contract and the Contractor shall carry out and bound by the same.

ii) During the currency of this contract, BGL can increase and/or decrease the number of the services / technicians to meet contractual requirements.

iii) Order the Contractor to remove or replace any workman whom the company considers incompetent or unsuitable and opinion of the company representative as to the competence of any workman engaged by the Contractor shall be final and binding on the contractor.

7. Contract Repatriation and termination

BGL shall reserves the right at any time during the currency of the contract, to terminate it by giving 30days notice to contractor, and upon expiry of such notice period the Contractor shall vacate the site / office occupied by him immediately.

However BGL shall reserve the right at any time during the currency of the contract, to stop/suspend the services under abnormal circumstances by giving one week notice to contractor. Payment shall not be payable for such period of suspension.

On normalisation, BGL may ask for resumption of services in week's period.

8. Compensation for non-fulfilment of obligation under Annual MaintenanceContract (AMC)

If the Contractor fails to provide the required services,

Break-down penalty would be applicable as follows:

A. For each Booster Compressor:

- **For Shutdown restored within 6 hours on daily basis - No Penalty. The service provider can also club 6 hours for two consecutive days for 2 times a month without any penalty.**
- **For Shutdown beyond 6 hours – Penalty @ Rs 200/- per hour for the default period; will be on monthly cumulative basis rounded to nearest hour. For calculation of default period, will be recorded jointly by the service provider and owner on daily basis.**
- **For carrying out the periodic / scheduled / breakdown maintenance of compressor package the service provider shall be allowed a maximum of 18 hours once in a month.**

Maximum penalty would be applicable 70% on monthly net invoicing amount of each Booster Compressor.

B. For each Dispenser:

- **For Shutdown restored within 6 hours on daily basis - No Penalty.**
- **For Shutdown beyond 6 hours – Penalty @ Rs 100/- per arm per hour for the default period; will be on monthly cumulative basis rounded to nearest hour. For calculation**

of default period, will be recorded jointly by the service provider and owner on daily basis.

- **For carrying out the periodic / scheduled / breakdown maintenance of compressor package the service provider shall be allowed a maximum of 24 hours for each arm of dispenser once in a month.**

Maximum penalty would be applicable 70% on monthly net invoicing amount of each Booster Compressor / Dispenser.

9. <u>General</u>

The operation &maintenance services shall be provided on round the clock basis.

a. The Contractor shall deploy adequate number of operators and technicians as well as tools & equipment for smooth and proper operation & maintenance of the compressors supplied in terms of the contract. In case required to meet operational requirements, the Contractor shall augment the same as per direction of Engineer-in-Charge.

b. The Contractor is required to carry out all services as mentioned in the Scope of Services and Schedule of Rates on all the 365 days including Sunday and all holiday and around the clock

c. The Contractor shall allow weekly rest and daily working hours to his workmen as per the relevant Act / Law / and Rule made there under. However, no work shall be left incomplete / unattended on any holiday / weekly rest. Technician / operator provided shall have minimum qualification of ITI. Contract in person or his authorized representative shall provide the services on daily basis to interact with Engineer-in-Charge and deployed workmen.

d. The workforce deployed by the Contractor for O&M services at CNG installation shall be of sound relevant technical professional expertise which is otherwise also essential from the safety point of view of the personnel of the Contractor as well as for the installation.

e. Contractor has to ensure the safety of man and machine all the times. Damages of equipment due to negligence will be recovered as per the decision of Engineer-in-Charge, which will be final.

f. Regarding work completion, the decision of the Engineer-in-Charge will be final and binding.

g. The Contractor shall make his own arrangements to provide all facilities like boarding and transport etc. to his workmen.

h. All personnel of the Contractor entering on work premises shall be properly and neatly dressed and shall wear uniform, badges while working on premises of the company including work sites.

i. Contractor shall maintain proper record of his working employee's attendance and payment made to them.

j. The Contractor's representative shall report daily to the Supervisor at BGL office through telephone from R.O. for day to day working.

k. All the safety rules and regulations prevailing and applicable from time to time at the installations as directed by BGL will be strictly adhered to by the contractor

l. The rates quoted by the Contractor must be inclusive of all taxes& duties except service tax. Service Tax to be quoted separately as specified in the SOR.

m. It will be the responsibility of the Contractor to pay as per the minimum wages of the appropriate government applicable under the Minimum Wage Act 1948.

n. The maintenance services shall be provided on round the clock basis. The Contractor is responsible to provide effective and efficient services round the clock and assure that there is no disruption in the services for want of any resources.

o. The Contractor shall deploy adequate number of technicians / operators at various site offices in consultation with Engineer-In-Charge to provide trouble free operation & maintenance of the compressors / dispensers. Site in charge shall always be available 24 hours on Mobile Phone.

p. All arrangements for communication from control room to the contract person working on job under the services shall be the responsibility of the contractor, viz pagers / walky-talky / telephone.

q. All the jobs mentioned under scope of services shall be carried out as per sound engineering practices, work procedure documentation, recommendation of the manufacturer and as per the guidelines / direction of engineer-in-charge of authorized representative.

10. Operation & Maintenance of compressor packages during contract period

a. All OEM spares, required for carrying out the operation and maintenance of the complete compressor packages and dispensers during the contract period, including periodic, breakdown maintenance for continuous and uninterrupted operation of the compressor packages shall be supplied by the contractor at free of cost to the owner.

b. The Contractor shall have to keep / supply all the consumables (particularly fill probes and its 'O' rings for dispensers), lubricants, coolant etc. required for carrying out periodic, breakdown, emergency maintenance etc. of the package so as to minimize the down time of the compressor/dispenser.

c. All tools, tackles and fixtures required for carrying out the above maintenance of the compressor shall be in scope of the Contractor. The scope will also include handling equipment like crane, forklift, chain pulley block etc. required during the any maintenance activity.

d. Any expert services required from principal company or OEM shall be arranged by the Contractor or his agent at his own cost. All arrangements like phone, fax, computer,

internet etc. required for correspondences with above personnel shall be arranged by the Contractor.

e. The periodic maintenance required to be done as per OEM recommendation shall be taken up promptly. The Contractor shall provide the detailed preventive maintenance schedule along with
   i) Estimated down time required for each type of maintenance schedule.
   ii) List of spares and their quantities required for each type of maintenance schedule per compressor/dispenser.
   iii) Type and number of man days required for each type of maintenance schedule per Compressor/dispenser.

f. The Contractor shall use only OEM's certified spares during maintenance. In case, the schedule maintenance of the OEM manual recommends checking and replacing parts like valves, regulators, hoses, piston rings etc. after certain time interval, same shall be replaced or used further only on approval from the BGL representative. However any unto ward consequences for non-replacement of such parts shall be the responsibility of the Contractor.

g. All routine and periodic checks / inspections required to be done as per OEM recommendation shall be done by the Contractor. Instruments required for above inspection like vernier calliper, micrometer screw gauge, fill gauges, bore gauge etc. shall be in scope of the Contractor and these instruments shall be calibrated every year.
h. The Contractor shall submit a copy of the daily / weekly / fortnightly / monthly / bio-monthly / quarterly and yearly performance report to the EIC in both soft and hard form. All stationery including the printed material shall be in scope of the Contractor.

i. All the maintenance / inspection job carried out by the Contractor shall be recorded and the report of the same shall be jointly signed by BGL representative.

j. The EIC will be final authority to take decision with regards to maintenance or replacement of spares or any disagreement between the Contractor and BGL, during the execution of the contract.
k. The Contractor shall carry out calibration of gas detectors and flame detectors every six months or earlier as per requirement or instruction of EIC of BGL. Also yearly calibration of all the instruments such as pressure gauges, transmitters, switches, mass flow meters etc shall be in the scope of the Contractor. In addition to the above all safety relief valves shall also be tested and calibrated every year.
l. Calibration shall be done from government-approved laboratories and shall be carried out at least 15 days prior to the calibration due date.
m. The periodic maintenance required to be done as per OEM recommendation shall be taken up promptly. The Contractor shall plan such maintenances during non peak hours and in consultancy with the EIC of BGL. Any maintenance that needs to be taken up shall be well planned in advance with due approval of the EIC. The scope shall include preparation of maintenance schedule for carrying out the maintenance during the contract period.

Brief Scope of Work:

1. Equipment under AMC

Comprehensive AMC proposed will be limited to the equipment listed under Vijayawada and Hyderabad CNG stations as per details given below:

Sr. No.	Name of Equipment & Make	Model & Brief Specification	Qty. (Nos.)
1	Booster Compressor Package of SAFE make	B 30-30 model of 250 SCMH capacity	13
2	CNG Car Dispenser of SAFE / ICL make	ESP 22/3 model of 15 Kg/min capacity	06

Other accessories like Radiator with motors and pumps, Air Compressors, Control panel etc. related to the Booster Compressor packages and Dispensers.

2. Contractor team (Technician / Operator) – Rolls and Responsibility:

The functions and responsibilities are listed below:

a) To function as an integral member of the BGL O&M coordination team.
b) Interface with Contractor / BGL on all equipment and system issues mobilize any Contractor / BGL resources required for scheduled or unscheduled maintenance.
c) Assist BGL personnel with development and implementation of sound operating and maintenance strategy and procedures, including corrective action guidance.
d) Assessments of consumables, operational and maintenance spares, OEM services etc. Maintain spares inventory well in stock to avoid any uninterrupted operations on round the clock basis.
e) Provide reports as per BGL O&M practices.
f) Conduct training programs for upgrading O&M resources, participate in all Contractor / BGL sponsored safety trainings.
g) Collect and provide data as deemed necessary by BGL to analyze equipment performance.
h) Responsible for performing all routine, breakdown & scheduled maintenance activities during O&M.
i) Monitor the performance of equipments.
j) Monitor all essential parameters of the running equipment and report any discrepancy in operational parameters.
k) Responsible for log book data capturing, minor maintenance activities, safety of equipments for safe operations.

Maintenance team shall be made available for work on 24 Hrs. basis.

3. Scope of work – Operation & Maintenance

3.1 Spares & Consumables

All Spares and Consumables like Frame oil, Air Compressor lube oil, Coolant, DM water, Gear box oil, Grease etc. will be in Contractor scope during the Comprehensive AMC period. BGL shall approve the installation of OEM equivalent spares; however contractor should submit all the technical details of equivalent spares to the concerned EIC prior to installation for approval.

3.2 Tools & Tackles

One set of conventional Mechanical & Electrical general tools for maintenance job shall be provided by Contractor.

3.3 Special Services

- Contractor shall arrange calibration of all the instruments which are installed in the package annually after necessary approval from BGL
- Contractor shall arrange filling of Co2 cylinders quarterly, however the flooding system function check with discharging the Co2 shall be carried periodically and recorded
- Contractor shall arrange visit of vendor representative for package routine maintenance depending on site requirement. Services like inspection, breakdown, top / major overhauls shall be taken care by contractor.
- Contractor shall arrange welder / plumber when required with material if required
- Contractor shall arrange Panel vendor / Software programmer visit when required with parts if required
- Contractor shall provide all necessary lifting equipment
- Contractor shall provide all necessary facilities of any additional repair, welding, testing, calibrations etc.
- OEM services if required for any Overhauls
- Maintenance of the instruments, transmitters, controls, switchgear with in the battery limit
- Contractor shall provide First Aid box at site
- Contractor shall provide painting of canopy and equipments annually / as and when required
- Contractor shall supply electrical system / panel which are damaged in case of power failure

3.4 Additional Services

Contractor shall provide any additional service that may be required, using the expertise and technology of OEM services and should provide a detailed inspection report

3.5 Scope for AMC Activities

Contractor shall depute site personnel as enlisted above for carrying out the AMC of the Booster compressor packages and Dispensers

Uninterrupted service shall be provided round the clock including Sundays and other holidays throughout the contract period. Contractor shall advise the schedule / predictive maintenance that need to be carried out and BGL will provide reasonable time period to carry out such work

Technician's activities are as detailed below:

1. All annual O&M spare parts (regular / breakdown / overhauling) will be in the scope of Contractor.

2. Round the clock trouble free and safe operation and maintenance of the following equipment as per laid down operating procedures
   a) Gas compressors, Electric motor, Cooling system, Overhead makeup coolant tank, Gas line with in the battery limit, Valves etc.
   b) Instrumentation – PTs, TTs, PGs, FTs, Electronic panels, Control valves, PSVs etc.
   c) Electrical panel, Radiator system, Air compressor system and Co2 flooding system.

3. Upkeep of all operational and maintenance records and everyday logging of all the critical parameters of equipment, hours run and any specific maintenance / repairs carried out including material / spares consumed

4. Continuous vigil on the condition of running equipment

5. Preventive maintenance schedule of all the equipment to be followed religiously using genuine OEM / OES spares and to be recorded in logbook

6. Fault finding and troubleshooting of the equipment are carried out and maintain the record of it

7. Schedule maintenance shall normally be carried out by interacting with Engineer in charge during day time general shift, however routine checks and maintenance to be carried out on round the clock

8. Upkeep of equipment shall be taken up immediately after completion of maintenance or a repair and area shall be kept neat and clean. The waste generated during maintenance shall be dumped in a designated area with in the CNG station

9. Provide the quality and adequate quantity of lubricating oils and cleaning agent as per OEM recommendations

10. Coordinate calibration of the instruments and maintain records

11. MIS duties – all Checklists, DPRs, Monthly reports miscellaneous correspondence regarding resource requirements and information required by management as and when required

12. Providing resources such as tools, cotton waste etc. as required for operations
13. Providing all personnel with the necessary PPE like Safety shoes, Hand gloves, Cotton uniform etc. and ensure that the personnel shall all the time use PPE when they are at site
15. Disposal of empty barrels / burnt oil barrels shall be disposed according to documented procedure.

16. All wastes (hazardous, bio-degradable & non-biodegradable) are stored & disposed off as per documented procedure

SECTION 9

SPECIAL CONDITIONS OF CONTRACT

1.0 GENERAL INFORMATION:-

The special conditions of contract shall be read in conjunction with general condition of contract(**GCC**), Schedule of rates, scope of work and any other document forming part of contract, wherever Context so Requires. **GCC** is available at tender issuing office and same shall be referred by Bidder. Notwithstanding, the subdivisions of the documents into separate sections every part of each shall be deemed to be supplementary of every other part and shall be read with and into the Contract so for as it may be practicable to do so. Where any portion of the special conditions of the Contract (**SCC**) is repugnant to or at variance with any provisions of the **GCC** then provision of **SCC** Shall be deemed to override the provision of **GCC** only to the extent of each repugnance or variations. In case of any contradictions the Decision of the Engineer-In-Charge will be final and binding on the Contractor.

1.1 In case of an irreconcilable conflict between Indian or other applicable standards, General Conditions of Contract, Special Conditions of Contract, Specification, Drawings or Schedule of Rates, the following shall prevail to the extent of such irreconcilable conflict in order of precedence:

i. Letter of Acceptance/ LOI along with Statement of Agreed Variations.
ii. Schedule of Rates as enclosures to Letter of Acceptance
iii. Special Conditions of Contract
iv. Service descriptions
v. Instruction to Bidder
vi. General Conditions of Contract
vii. Indian Standards
viii. Other applicable standards

2.0 Payment Terms:

Monthly running account bills in triplicate subject to carrying out maintenance as per the scope of the work. Payment shall be made from the F&A Dept. of BGL, within 15 days from the date of receipt of the bill. The bill should be submitted along with the copies of all monthly reports like scheduled maintenance, statutory testing reports, service reports and other relevant reports as necessary duly certified by station In-Charge/Engineer-In-Charge.

3.0 Contract Performance Guarantee:

Within 30 days of the receipt of the notification of award (LOI/WO) from the OWNER, the successful bidder shall furnish the Performance security in accordance with provision of contract in the form provided in the bid document for 28months from the date of Work Order.

The Performance security shall be for the amount equal to 7.5% of one year's contract value (excluding taxes & duties) of the contract awarded towards faithful Performance of the contractual obligations and Performance of services. The Performance security shall be in the form of Crossed Demand Draft/Banker's Cheque or Bank Guarantee in favor of BGL, Hyderabad. Bank Guarantee shall be from any Indian scheduled commercial bank or a branch of an International bank situated in India and registered with Reserve Bank of India as scheduled foreign bank in case of Indian bidder and from any reputed International bank or

Indian scheduled commercial bank in case of foreign bidder. However, other than the Nationalized Indian Bank, the bank whose BG are furnished, must be commercial banks having net worth in excess of Rs. 100 crores and a declaration to this effect should be made by such commercial bank either in the bank guarantee itself or separately on a letter head, as per proforma enclosed in the Tender Document.

The Bank Guarantee shall be valid for a period of 28 months from the date of issue of LOI / WO.

The Bank Guarantee will be discharged by BGL not later than 3 months from the date of expiration of the seller's obligations under the contract. Defect Liability Period (DLP) is 3 months from the date of completion of the contract.

Failure of the successful bidder to comply with the requirements of this article shall constitute sufficient grounds for the annulment of the award and forfeiture of the bid security, in which event the OWNER may award the order to the next lowest evaluated bidder or call for new bids at its discretion at the risk and cost of the successful Bidder.

4. CONTRACT PERIOD:-

The Contract shall be Valid for a Period of Two years from the date of Issue of work order (or) the letter for deployment from BGL's EIC.

5. Not Applicable.

6. Extension of Contract:

The contract may be extended for a maximum period of one year at the sole discretion of BGL, subject to satisfactory performance of the Vendor during the two years contract period.

7. Site Information: As mentioned in Material requisition at Hyderabad, Vijayawada and Kakinada.

8. TAXES AND DUTIES:-

a. Income tax at the prevailing rate as applicable from time to time shall be deducted from contractor's bills as per Income tax Act, and quoted rates shall be deemed to include this.
b. The contractor agrees to and does hereby accept full and exclusive liability for the payment of any and all taxes, duties etc now in force and hereafter increased, imposed or modified from time to time in respect of works and materials.
c. The Contractor agrees to and does hereby accept full and exclusive liability for the payment of any and all taxes, duties, including Goods & Service Tax (GST), custom duty, Input Tax Credit (ITC), octroi etc. now in force and hereafter increased, imposed or modified from time to time in respect of works and materials and all contributions and taxes for unemployment compensation, insurance and old age pensions or annuities now or hereafter imposed by any Central or State Government authorities which are imposed with respect to or covered by the wages, salaries, or other compensations paid to the persons employed by the Contractor and the Contractor shall be responsible for the compliance with all obligations and restrictions imposed by the Labour Law or any other law affecting employer-employee relationship and the Contractor further agrees to comply, and to secure the compliance of all sub-contractors with all applicable Central, State, Municipal and local law and regulation, and requirement of any central, State or Local

Government agency or authority. Contractor further agrees to defend, indemnify and hold Employer/Consultant harmless from any liability or penalty which may be imposed by the Central, State or Local authorities by reason of any violation by Contractor or Subcontractor of such laws, regulations or requirements and also from all claims, suits or proceedings that may be brought against the Employer/Consultant arising under, growing out of, or by reason of the work provided for by this Contract, by third parties, or by Central or State Government authority or any administrative sub-division thereof.

d. Employer shall make from Contractors bills such tax deductions as are required as per rules and regulations in force from time to time.

9. RECOVERY:-

Cost Of any Damage /loss of the property of **BGL**, by the contractor shall be recovered from the Bill / security deposit of the contractor and decision of the **BGL / EIC** in this regard shall be final Binding and conclusive.

10. RIGHT TO GET SERVICES CARRIED OUT THROUGH THEIR AGENCIES

Nothing contained herein shall restrict BGL from accepting similar services from other agencies, at its discretion and at the risk and cost of the contractor, if the contractor fails to provide the said services any time.

11. SAFETY & SECURITY

The contractor shall provide proper cotton dresses (Uniform), safety shoes and to provide safety kit as per requirement. No contractor's personnel shall be allowed on duty without wearing applicable Safety gears. Contractor should also ensure police verification of the personnel before deploying them. The same is to be submitted along with the Bio-data.

The contractor shall provide signed photo identification cards for his personnel to be deployed with in **BGL'S** premises. The contractor shall obtain proper gate passes for men/ materials from BGL's Security department.

12. THE ENGINEER –IN-CHARGE/ OFFICER IN CHARGE SHALL HAVE POWER TO

i) Issue the Contractor from time to time during the running of the contract such further instructions as shall be necessary for the purpose of proper and adequate execution of the contract and the Contractor shall carry out and bound by the same.

ii) During the currency of this contract, BGL can increase and/or decrease the number of the services to meet the work requirements.

13. Validity of Quoted Rates:

The Rates Quoted accepted shall remain valid for the entire period of Contract and no escalation whatever shall be permissible after award of the contract except for the statutory variation due to Goods & Service tax.

The quoted Rates shall be inclusive of all Taxes & Duties applicable during the Contract period **Except for Goods& Service tax (GST)& Education Cess thereon. GST**&Cess, if any, thereon shall be paid extra, if applicable, on submission of documentary evidence / invoice(S).

The Bidder shall indicate in the bid the Goods & Service tax Registration (Provisional) Number.

The above details are required to enable BGL to avail Input Tax Credit(ITC) as per GST Acts/ Laws.

Please note that responsibility of payment of GST lies with service provider.

SECTION 10

SCHEDULE OF RATES (SOR)

BHAGYANAGAR GAS LIMITED	**Comprehensive Annual Maintenance Contract (AMC) Services for M/s ICL/SAFE make Booster Compressors and CNG Dispensers at Hyderabad, Vijayawada and Kakinada** **Bid Document No. BGL/399/2017-18**	VOLUME II OF II

Schedule of Rates (SOR)

Tender No: BGL/ 399/2017-18

Item: Tender for Comprehensive Annual Maintenance Contract (AMC) Services for M/s ICL/SAFE make Booster Compressors and CNG Dispensers at Hyderabad, Vijayawada and Kakinada.

S.No	Description	Make of Compressor	No of compressors (Qty)	Proposed Period (Service Months)	Unit rate incl. of all taxes & duties,but excl. of GST (Rs.)	Total amount incl. of all taxes and duties , excl of GST (Rs.)
A	**Booster Compressors**					
	Comprehensive Annual Operation and Maintenance of (M/s. SAFE OR ICL) make and its accessories including all consumables, spares, Manpower , lubricants, carrying out regular,periodical and Breakdown maintenance as per OEM's specification etc., excluding electricity power charges at following locations:					
1	M/s. Hayath Filling Staion, Hayath nagar,Hyderabad (26.02.2018 to 25.02.2020)	(M/S. SAFE OR ICL make)	1	24		
2	Sapthagiri Filling Station, Meerpet, Hyderabad(26.02.2018 to 25.02.2020)	(M/S. SAFE OR ICL make)	1	24		
3	Lalitha Devi Petrol Pump, RP Road, Hyderabad(26.02.2018 to 25.02.2020)	(M/S. SAFE OR ICL make)	1	24		
4	Sri Chakra Filling Station, Nampally, Hyderabad(26.02.2018 to 25.02.2020)	(M/S. SAFE OR ICL make)	1	24		

5	Sri Srinivasa Service Station, Ramavarappadu, (02 nos.) Vijayawada(26.02.2018 to 25.02.2020)	(M/S. SAFE OR ICL make)	2	24		
6	Ravindra Oil Company, Bhavanipuram, Vijayawada(26.02.2018 to 25.02.2020)	(M/S. SAFE OR ICL make)	1	24		
7	Radhakrishna Service Station, Tadepalli, Vijayawada(26.02.2018 to 25.02.2020)	(M/S. SAFE OR ICL make)	1	24		
8	South Central Railways, Diesel loco shed (as per the EIC intimation)	(M/S. SAFE OR ICL make)	1	24		
9	APSRTC, Ibrahimpatnam-II Depot (02 nos. Boosters), Vijayawada (26.02.2018 to 25.02.2020)	(M/S. SAFE OR ICL make)	2	24		
10	JP Fuels, Cinema Road, Kakinada(01.09.2015 to 31.08.2017)	(M/S. SAFE OR ICL make)	1	24		
11	M/s. Swami auto care Nadakuduru (26.02.2018 to 25.02.2020)	(M/S. SAFE OR ICL make)	1	24		
					Subtotal amount incl. of all taxes & duties. (A)	
					Goods & Service Tax, GST @ …., Rs.	
					Total amount inclusive of all taxes and duties for AMC of Booster Dispensers, Rs. (Words),A	
B	**Dispensers**					
	Comprehensive Annual Operation and Maintenance of (M/s. SAFE OR ICL) make Dispensers and its accessories including all consumables, spares, Manpower, carrying out regular, periodical and Breakdown maintenance as per OEM's specification etc., excluding electricity power charges at following locations					
1	BGL Mother station (02 nos. dispensers), Vijayawada	(M/S. SAFE OR ICL make)	2	24		

2	Sri Srinivasa Service station, Ramavarappadu, Vijayawada	(M/S. SAFE OR ICL make)	1	24		
3	Basaveswara Filling station , Ajitsingh nagar (02 n os. Dispensers), Vijayawada	(M/S. SAFE OR ICL make)	2	24		
					Subtotal amount incl. of all taxes & duties. (A)	
					Goods & Service Tax, GST @ …., Rs.	
					Total amount inclusive of all taxes and duties for AMC of Dispensers, Rs. (Words), B	
					Grand Total amount inclusive of all taxes and duties for AMC of Booster Compressors and Dispensers, Rs. (Words), A+B	

Note:

- All the Pages of the Schedule of Rates should be signed and stamped by the bidder.
- Bidder should quote exactly as per the format specified in Schedule of Rates.
- Evaluation shall be done on overall least cost to BGL.